



Report on Working Group # 2 The MU2E detector: calorimeter

S.Miscetti
LNF INFN Frascati


MUSE Scientific Board meeting 20-Dec-2019



Summary of "n" SiPM tests with Laser

Time resolution vs Pulse Height






- First estimate is that one single sensor will get around 800 ps resolution at $5x10^{11}$ n/cm² for an energy deposit of O(30 MeV).
- Factor of sqrt(2) achieved using two sensors/crystal → 560 ps , close to requirement





Progress N.1: FEE CRR

- ☐ CRR for rad-hard FEE and FEE-Mezzanine cables done Nov 18 2019
- □ 20 FEE prototypes + 5 MB prototypes and 7 x 4 FEE-MB cables in hand
- □ Integrated test done last week with 4 of these prototypes up to a TID of 100 krad → Amplifier, HV-regulator and DAC (to set HV) OK
 - → ADC (read HV, T and Id) show drifts on readout. Recovered with calibration
 - → unexpected loss of 1 MOSFET for the two boards with HV OFF
- → Requires another round of irradiation after having selected the DAC/ADC lot
- **→** B-Field test completed successfully




Progress N. 2: FEE tenders

- TENDERs for 3500 FEE boards done last week from INFN
 - → Firm selected (ARTEL SPA)
 - → 10 prototypes for rad-hard test in January
 - → Pre-production of 350 pieces in February
 - → Full production of 3150 pieces in spring
- Tender for 840 (x 4) SIPM/FEE/MB cables done last week from INFN
 - → Cables will be produced by SAMTEC as for the prototypes tested in the last 4 months
 - → Outgassing/Radiation/B-Field tests OK
 - → Routing path tested in Mockup




Progress N. 3: DIRAC V2 prototypes



DRAC V2 DA-04(23-VI

- FPGA PolarFire Rad-Hard
- VTRX readout (TDAQ)
- Analog Input and ADC firmware as in V1
- 5 assembled boards ready in Pis



Test In progress both for Board functionality + Vertical Test with TDAQ





Progress N. 4: Calo Assembly Room




- Practically completed
- Access with crane for Calo truck loading
- Temperature and Humidity controlled and monitored
- Portable crane inside for components
- One mechanical assembling region
- One electrical and data acquisition region
- Testing of half disk a time

- Nitrogen and compressed air installed
- Electrical implant finished
- fire alarms done
- calibrating HEPA and HVAC system
 - sealing small openings
 - cleanroom class verification



Progress N. 5: Laser system



- ☐ Pre-production fiber bundle with 110 quartz-quartz-fiber delivered (tested up to 100 krad, outgass in progress, very good bundle uniformity of ± 6%)
- ☐ Routing test done in mockup. Handling resulted to be easy with uniformity unmodified after handling.





Progress N. 6: SiPM-glueing procedure OK

- ☐ Tooling for starting gluing procedure delivered from LNF to Sidet
- ☐ Small production of "pre-mixed" EP30AN from MasterBond done
- ☐ Pre-production test done at end of November
- Production of SiPM holders started
- ☐ SiPM/Glueing operation scheduled for Feb 2020 in Sidet
- 25 Holders/tooling x 2 tooling x 2 runs/day =
 100 Holders/day → 15 working days, 1 month operation











Deliverables & Milestones

- → D2.1 (TDR) Month 12
- → D3.3 (Design Laser system) Month 18
- → D4.2 (Development of Simulation Code) Month 32
- → D2.2 (Production DB for Crystals and sensors) Month 36
- → MS2 (Assembly of the first calorimeter disk) Month 42

Calorimeter disk assembly delayed of more than 1 year

- → CRR of mechanics done in May 20
- → CRR review for FEE Completed/proto MB/DIRAC V2 arrived
- → PCB review and CRR of MB/DIRAC for Feb 2020
- → Complete Disk mechanics expected for late spring 2020
- → FEE delivery expected for late spring 2020
- → Assembly start now planned for late spring 2020
- → it will still be a great result to have the aluminum disks at FNAL for Feb 2020









